# 4743a

Diag Cht. No. 905 Form 504 U. S. COAST AND GEODETIC SURVEY DEPARTMENT OF COMMERCE DESCRIPTIVE REPORT Type of Survey Idydrographic
No 474334B LOCALITY LIBRARY & ARCHIVES DATE ....

6. 4.8. SURVEY . & A. MAT. 6 1928

# DEPARTMENT OF COMMERCE U.S. COAST AND GEODETIC SURVEY E. LESTER JONES, DIRECTOR.

DESCRIPTIVE REPORT

to accompany

HYDROGRAPHIC SHEET # 2 + 474

VIRGIN ISLANDS

S.S. RANGER

G.C.MATTISON
C.K. GREEN,
Chief of Party.

1923-24

## DESCRIPTIVE REPORT

## to accompany

## HYDROGRAPHIC SHEET #2.

Original instructions dated June 22, 1925.

# LIMITS:

Hydrographic sheet #2 includes waters surrounding St. John Island and the eastern end of St. Thomas Island, with the exception of areas adjoining British possessions. The work in the Narrows was carried across the entire channel. The sheet has as its approximate limits, meridians 64° 37° and 64° 55°, and parallels 18° 14° and 18° 25°.

## METHODS:

Control was furnished by triangulation and topographic surveys made by the party inder Lieut. G.W. Swainson, H. & M. Engineer previous to 1925. Hydrographic signals were located by the hydrographic parties.

The RANGER, launches MARINDIN and MITCHELL, the wire drag tender and the motorudinghy were used in this survey. For all inshore work the hand lead was used. For generally deep areas, the hand lead and trolley rig was used and for those areas too deep for the hand lead the sounding machine with stranded wire was employed.

## CURRENTS:

See report for Wire Drag Sheet #2 for information on currents in this vicinity.

### TIDES:

All tadal data may be obtained from the report for Wire Drag Sheet #2.

# COMPARISON WITH CHART AND WIRE DRAG SURVEY:

In making a general comparison between the hydrographic sheet and chart very few evident differences were found. Following are those that were noted.

A depth of 8-3/4 fathoms was found 1.75 miles 56° true from Frenchman's Cap where 12 fathoms is now shown.

The four fathom shoal west of Steven Cay marked P.D. was not found during this survey.

The least depth found on Eagle Shoal was two feet.

In a number of places, shoal soundings as shown on the chart were not found during the hydrographic sourvey. These, however, were later verified during the wire drag survey.

In practically all cases, soundings obtained by wire drag were less than those obtained during the hydrographic survey and in some cases very much so. In some instances the soundings checked but a deffer ence in location or extent of the shoals as found by both surveys was noted.

Some of the more important differences are noted below:

A depth of 24.5 feet was found 1085 meters 1120 true from / Cabrita Point, where 8-1/2 fathoms is now shown on the hydrographic sheet. The chart however, shows 4-1/4 fathoms.

A depth of 23.5 feet was found 815 meters, 3050 true from Coki Point where 7-1/4 fathoms is now shown on the hydrographic sheet.

A depth of 27.5 feet was found 280 meters 1820 true from the southern end of Steven Cay. This plots near 10 fathoms sounding on hydrographic sheet.

Soundings of 24 feet, 34 feet and 18 feet were found where 8-3/4 fathoms is shown on the hydrographic sheet north of Durloe Cays in Lat. 18 21° - 1036 meters, Long. 64 47° - 1337 meters.

The sunken rock plotted west of Johnson Reef on the smooth hydrographic sheet does not exist. This area has been dragged to an effective depth of 18 feet.

A least depth of 23 feet was found on the shoal south of Whistling Cay during the hydrographic survey, while the drag sheet shows 17-1/2 feet.

A depth of 24.5 feet was found 937 meters 72° true from  $\sqrt{}$  Ditlef Point, where 7 fathoms is now shown on the hydrographic sheet.

A depth of 28.5 feet was found 955 meters 2770 true from White Point where 7 fathoms is now shown on the hydrographic sheet.

The 14 and 15 foot soundings, 751 meters 313° true from Lagoon Point plot on the 5 fathom curve as shown on the smooth hydrographic sheet.

There are also differences between the results shown in deeper areas south of St. Thomas.

## NOTES MADE WHEN PLOTTING:

Cuts from launch to signal YEL failed to intersect within reasonable distance of any one definite point. Positions 1 to 34 % tender, were transferred from the boat sheet by order of the Commanding Officer. Present position of signal "YEL" on smooth sheet was taken from Wire Drag smooth sheet #2.

A few positions on the north coast of St. John Island plot on shore, questioning plotted position of signal "MED", takenfrom Wire Drag Smooth Sheet #2. Cuts to this signal were plotted as a check again on this sheet.

The shoal soundings in very closely developed areas have been placed in parenthesis, beyond the shoreline near the area developed. These soundings are given in fathoms and fractions thereof with a line to the location of the sounding.

Signals on this sheet were plotted by J.M.Baker and checked by W.R.Porter and B.H. Rigg. It was found necessary to transfer some of the hydrographic signals from the bhat sheet as the cuts were not sufficient.

Soundings and positions were plotted by J.M. Baker.

In volume #9, positions 63 and 64 b werenot plotted

## ANCHORAGES:

They are adequately described in the Coast Pilot.

## LANDMARKS:

In addition to those landmarks listed in the report for Wire Drag sheet #2 there is the Reform School on Leinster Point, St. John Island setting approximately 250 meters back from the end of the point at an elevation of 200 feet. This is a brick building and visible from the east ward and some distance to the westward on the channel between Tortola and St. John, Pat. 18 22° 87 meters, Long. 64 43° 338 meters.

Respectfully submitted.

Carl F.Ehlers, Jr. H&G.Engineer.

G.C. Mattison, Chief of Party

# STATISTICS HYDROGRAPHIC SHEET 2

_	Date	Letter	Vol	Pos.	Sd.gs.	Miles Stat.	Vessel.
	12-18-23	A	1	95	221	18.4	Marindin
	12-26-23	B	1	42	111	13.5	=
	12-29-23	C	1	45	92	9.8	<b>n</b>
	1- 15-24	D	1	71	205	12.0	• • • • • • • • • • • • • • • • • • •
	1- 15-24	A	2	64	115	12.1	Mitchell
	1- 16-24	В	2	129	271	20.0	<b>*</b>
	1-16- 24	12	1	94	259	17.0	Marindin
	- 15-24	F	1	74	223	18.0	* .
	1- 17-24	C	2	119	189	14.5	Mitchell
	1- 18-24	D	2	49	71	7.0	<b>#</b>
	1- 18-24	<u>G</u>	3	28	83	2.0	Marindin
	1- 21-24	H	3	53	96	17.0	<b>.</b>
	1-,21-24	<u> </u>	6	83	85	21.0	Ranger
	1- 22-24	E	284	142	141	26.0	Mitchell
	1- 22-24	J	3	122	234	20.0	Marindin
	1- 23-24	K	3	135	274	20.0	Mitchell
	1- 23-24	F	4	99	141	17.0	Marindin
	1- 24-24	L	3	124	263	21.5	Mitchell
	1- 24-24	G	4	100	2 <b>94</b> 28	17.2 5.0	RANGER
	1- 24-24	B H	6 4&5	25 137	20 <b>5</b>	26 <b>.</b> 5	Mitchell
	1- 25-24 1- 25-24	M	7	51	97	18.5	Marindin
	1- 28-24	J	5	127	163	29.1	Mitchell
	1- 28-24	n	7	46	84	18.0	Marindin
	•	K	5	73	105	19.0	Mitchell
	1- 29-24 1- 29-24	P	7	86	167	<b>30.0</b>	Marindin
	1- 30-24	Ĺ	5	26	34	5.7	Mitchell
	1- 30-24	- ସ	7	113	279	26.5	Marindin
	1- 31-24	R	7	102	225	27.0	Marindin
	2- 1-24	M	5	98	140	25.8	Mitchell
	2- 1-24	C	6	42	42	9.4	RANGER
	2- 5-24	D	6	48	68	10.2	.#
	2- 18-24	B	6	14	14	2.9	Ħ
	Z- 19-24	f	6	20	20	4.1	
	2- 21-24	G	6	32	32	6.7	•
	3- 27-24	H	6	108	108	28.9	₩
	3- 28-24	S	7	26	32	4.0	Marindin
	9- 24-24	J	8	185	185	<b>57.</b> 0	RANGER
	9- 24-24	a	9	121	245	11.0	Tender
	9 25-24	K	8	196	229	47.1	RANGER
	9- 25-24	ъ	9	90	220	10.0	Tender
	9- 26-24	L	8	180	225	47.0	RANGER
	9- 26-24	C	9	98	230	12.5	Tender
	29-24	M	8	91	108	24.5	RANGER
	29-24	đ	9	69	226	9.0	Tender
	9- 30-24	•	9&11	141	325	19.0	Tender
	9- 30-24	N	15	123	185	59.7	RANGER
	10- 1-24	8.	10	153	699	15.6	Motor dinghy
	10 1-24	35	11	183	421	23.0	Tender Water dinghy
	10- 2-24	þ	10&12	152	575	12.8	Motor dinghy
	10- 2-24	T	11	102	172	30.5	Marindin

Statistics
Hydrographic Sheet #2

Date	Letter	Vol.	Pos.	Sdgs.	Miles Stat.	Vessel
<b>MO- 3-24</b>	υ	11	47	86	13.0	Marindin
10- 3-24	N	12	58.	169	11.7	Mitchell
10- 6-24	g	11&13	104	300 .	10.0	Tender
10- 7-24	h	13	122	354	13.0	₩
10- 8-24	j	13	127	168	16.0	Ħ
10- 9-24	C	12	111	608	13.5	Motor dinghy
10-9-24	k	13	124	236	24.0	Tender
10-10-24	ď	12	103	564	10.0	Mittell Motor Dingby
10-10-24	1	13&14	130	411	20.0	Tender
10-20-24	111	14	103	218	12.0	•
10-24-24	e	18	70	281	6.9	Motor dinghy
10-28-24	P	15	51	51	9.2	RANGER
10-29-24	Q	15	183	280	25.8	w
10-30-24	R	15	187	249	17.8	**
11- 4-24	4	14	111	208	22.0	Marindin
11- 4-24	f	18	139	462	11.0	Motor dinghy
11- 5-24	W	14	69	138	13.0	Marindin
11- 5 <del>p</del> 24	n	17	151	383	13.4	Tender
11- 6-24	Y	14	87	205	16.0	Marindin
11- 6-24	р	17	102	197	8.3	Tender
11- 7-24	Š	15	123	130	11.3	Ranger
11-10-24	T	16	38	<b>38</b>	8.0	w
11-17-24	σ	16	104	1 <b>84</b>	9.0	109
11-25-24	7	16	149	277	20.0	**
11-26-24	q	17	68	115	9.0	Tender
11-26-24	ğ	18	81	391	5.3	Motor dinghy
11-28-24	r	17	78	280	8.8	Tender
12-10-24	3	17	60	<b>3</b> 16	9.0	**
		Total	7677	16399	1305.8	

Area surveyed 163.5 square stat.miles.

## TIDE DATA

Three tide staffs were established in Little Cruz Bay at different times for tides in Pillsbury Sound and vicinity.

Two staffs were established in Francis Bay for the area north of the sound except the area at the western edge of sheet around Hans Lollick Island which is referred to staffs in Magens Bay. Automatic tide gauges in St. Thomas Harbor used for area south of St. Thomas. One tide staff and one automatic tide gauge were maintained at different times in Coral Bay for the area on eastern part of sheet.

# ST. THOMAS TIDE GAUGE:

,	- <del></del>					
***	Plane of reference	M.T.L.	-0.5 ft	5.2 0	n s	taff
• •	Lowest tide observed		•	4.9	77	11
•	Highest tide observed		<b>)</b>	6.8	11	**
MAGENS BAY TID	E STAFF #1:		•			
	Plane of reference	M.T.L.	-0.5 ft	5.93	on i	taff
	Lowest tide observed			5.4	Ħ	11
	Highest tide observed		*	7.8	77	**
MAGENS BAY STA	FF #2:		ž			
	Plane of reference	M_TIL	-0.5 ft.=	1.5	**	17
	Lowest tide observed		*	1.0	**	**
	Highest tide observed		i	2.7	11	#
LITTLE CRUZ BA	Y STAFF #1:					
	Plane of reference	M.T.L.	-0.5 ft.=	2.55	11	11
	Lowest tide observed			2.3	**	16
	Highest tide observed			4.0	н	#
LITTLE CRUZ BA	Y STAFF #2;					
	Plane of reference	M.T.L.	-0.5 ft.=	2.4	19	**
	Lowest tide observed			2.4	Ħ	**
	Highest tide observed			3.5	10	**
LITTLE CRUZ BA	Y STAFF #5:					
	Plane of reference	M.T.L.	-0.5 ft	1.2	17	n
	Lowest tide observed		-	0.7	17	**
	Highest tide observed			2.2	11	**
FRANCIS STAFF	<u>#1</u> :					
	Plans of reference	M.T.L3	-0.5 ft	2.83	11	17
	Lowest tide observed			2.1	17	**
	Highest tide observed			4.0	Ħ	**

# TIDE DATA #2

# FRANCIS BAY STAFF #2:

Plane of reference Lowest tide observed Highest tide observed	M.T.L.	<b>99</b> 5	ſŧ,	=	1.4 1.2 2.8		on #	staff "
CORAL BAY STAFF #1:								
Plane of reference	M.T.L.	<b>-</b> 0 <sub>•</sub> 5	ft.	=	1.45	, 17	11	П
Lowest tide observed		-			1.2	*	**	**
Highest tide observed					2.8	##	11	**
CORAL BAY STAFF #2:								
Plane of reference	M.T.L.	-0.5	ft.	=	1.6	11	11	11
Lowest tide observed					1.3	12	**	**
Wibhast tide abserved					2.1	17	17	19

Name	L	at.	D.M.	Lo	ng.	D.P.	<del> </del>	Rema	rks.	<u> </u>	·	
Rug	18	18		64	53		Topo_	Trans	fer	red :	from	bromide.
Bov	18	18		64	53		#		**		**	**
Neck	18	18		64	53		11		17		Ħ	99
Crop	18	18		64	52		**		**		**	71
Bo	18	18	734	64	52	346	Hydro	•	Ŧ		¥	*
Lag	18	18	1420	64	52	620			erre	d f	rom :	boat shee
Com	18	19	100	64	51	1645		cated				
Can	18	19	302	64	51	1442	**	17	17	19		
Say	18	19	300	64	51	1268	**	#	17	11		
Will	18	19	446	64	51	455	17	**	77	17		
Try	18	19	150	64	51	366	11	17	24	#		
Go	18	18	1618	64	50	1503	11	11	17	44		
Well	18	19	459	64	50	260	10	**	11	17		
Вор	18	19	<b>67</b> 5	64	50	930	11	17	77	**		
Fid	18	19	1100	64	50	572	n	19	**	18		
riu Gel	18	19	1160	64	51	267	98	11	70	W		
	18	19	1160	64	5 <b>0</b>	201	Tono.	trans	fer	red	from	bromide.
Temp Neb	18	20	1550	64	5 <b>1</b>	1580		. loca				OZ UMZWU (
	10	20	1550	04	91	1960	пуато	• 100a	, ve u	<b>.</b>	CUCS	
Turtle Back rock	10	20	1676	64	51	920	14	11		77	10	
		20 21	00	64	52	520 57	11	**	,	**	**	
Ki Thatch	18 18	21	00	64	52 51	31	Mwien	gulati	٥n			
			3064	64	5 <b>0</b>	710		• Loca		hv	anta	
Step	18	21	1064				ayaro	- Hoca		U.y	11	•
Sag	18	21	1428	64	49	674	11	₩		10	**	
To	18	21	1363	64	48	1673		**		11	11	
Gas	18	22	412	64	48	460	17	71		**	11	
Pit	18	22	352	64	48	85				••	••	
Carv	18	22		64	47			gulati				
Lit	18	20	1640	64	46	1376	•	• Loca		-		
Kim	18	21	535	64	45	1020	**	*1		11	77	
Ench	18	22	320	64	44	1362	19	Ħ		**	***	
Staff	18	21		<b>64</b>	44							bromlde
Bre	18	21	1743	64	44	312	•	. loca		•		
Nab	18	21	1700	64	43	<b>1</b> 55 <b>6</b>		-				oat sheet
Bal	18	21	1580	64	43	577	<b>"</b> 1	ocated	. by		8	
Ter	18	22	330	64	43	425	H	**	**	**		
Rest	18	22	50	64	43	378	**	11	11	79		
Tooth	18	22	223	64	42	1232	Ħ	**	17	rt		
Gre	18	22	47	64	42	848	11	**	**	**		
<b>Ž</b> in	18	21	1392	64	42	171	17	**	**	Ħ		
Beck	18	21	515	64	41	186	11	11	11	**		
Per	18	20	1272	64	<b>\$</b> 0	950	ri	17	77	**		
Do	18	20	1490	64	40	1480	**	#	Ħ	**		
Hab	18	20	1704	64	40	1526	11	15	11	•		
Gav	18	20	1700	64	41	24	**	**	**	**		
Vel	18	20	1736	64	41	210	17	***	11	11		
	18		1370	64	41	490	77	**	17	•		
Slope		20					11	17	**	11		
Fag	18	20	1586	64	41	1018	**	10	11	11		
Ed	18	20	1786	64	41	802		17	17	17		
Kee	18	21	190	64	41	593	11	**	74	11		
Rek	18	21	143	64	41	1098	11	₩	44	**		

++++	*_*_ <sup>;</sup>	*_*_*	Sie	mals .+_+_+.			*_*_*_*_*_*
Name	L:	at. *-*-*-	D.M.	Lo	ng.	D.P.	Remarks
Ot	18	21	350	64	41	<b>86</b> 0	Hydro. located by cuts
Slim	18	18	1571	64	42	250	·
Mal	18	21	650	64	41	975	
Fat	18	18	1150	64	42	212	
Dus	18	21	780	64	41	853	
Bol	18	18	200	64	42	406	
Dok	18	21	820	64	42	26	
Sou	18	18	940	64	42	935	
Em	18	20	1830	64	42	1475	
Nor	18	18	1073	64	42	850	
Rush	18	19		64	43		Topographic
Wye	18	19	360	64	44	756	Hydro. located by cuts.
Man	18	19	1010	64	44	1452	
Rock	18	19	320	64	45	1375	
Dead	18	19	746	64	45	1720	
Fen	18	19	44	64	45	1628	
Dit	18	18		64	45		Triangulation
Git	18	19	660	64	46	774	Hydro, located by cuts
Now	18	19	00	64	47	193	
Out	18	19	196	64	47	54	
Go	18	19	334	64	47	117	
Bake	18	19		64	47		Triangulation
Ma	18	19	<b>327</b>	64	47	960	Hydro. lecated by cuts
Gun	18	19	622	64	47	435	
Gin	18	19	930	64	47	713	
Big	18	19	1654	64	47	1710	" transferred from boar sheet
Law	18	19	1800	64	47	1630	
Gal	18	19	1800	64	47	1610	
Dock	18	19	1807	64	47	1309	" located by cuts.
Jo	18	20	360	64	47	1635	17 19 17
Came 1	18	20		64	45		Topographic
l'ap	18	21	160	64	43	570	Hydro. located by cuts
Ten (Tent)	18	23	861	64	41	710	17. 11 11 11
Brit	18	22		64	42		Triangulation
Fr.Thatch	18	23		64	44		<u> </u>
Met	18	16	1350	64	53	1660	Hydro. located by cuts
<u>qi</u> d	18	16	1272	64	53	1362	
S <b>o</b>	18	16	1015	64	53	435	
(in	18	16	1275	64	53	293	

#### DEPARTMENT OF COMMERCE

AND REFER TO NO. 11-DRM

## U. S. COAST AND GEODETIC SURVEY

WASHINGTON

September 27, 1928.

F-

## SECTION OF FIELD RECORDS

Report on Hydrographic Sheet No. 4743a.

St. John and East End of St. Thomas, Virgin Islands

Surveyed in 1923-1924

Instructions dated June 22, 1923 (RANGER)

Chief of Party, G. C. Mattison.

Surveyed by party of Steamer RANGER.

Protracted and soundings plotted by J. M. Baker, Jr.

Verified and inked by J. D. Torrey.

- 1. The records conform to the requirements of the General Instructions.
- 2. The plan and character of development conform to the requirements of the General Instructions.
- 3. The plan and extent of development satisfy the specific instructions.
- 4. The sounding line crossings are adequate.
- 5. The information is sufficient for drawing the usual depth curves.
- 6. The usual field plotting was done by the field party and where this part of the work could be identified was found accurate but the sheet had become so rubbed and soiled that in numerous cases, especially in the closely developed areas, the soundings were partially or completely obliterated and could not be made out. Also, the positions, day and number, particularly where green ink was used, were completely gone; this necessitated more than the usual checks to follow lines.
- 7. The overlap with sheet H. 465la shows some open areas but as the contemporary wire drag sheet H. 4743b covers this area, additional work does not appear warranted.

- 8. The shoal areas are well and closely developed.
- 9. The bays and small indentations could have been better developed on a scale of 1:10,000.
- 10. The character and scope of the survey are excellent and the drafting, so far as is possible to judge, is also excellent.
- 11. Reviewed by J. D. Torrey.
- 12. Sheet inspected by A. L. Shalowitz (See notes attached).

## Additional Notes on H. 4743a

- 1. The following notes will be found pertinent to the adequacy and completeness of the work covered by this sheet.
- a. In lat. 18° 19' 140 m., long. 64° 49' 420 m., a 40-foot sounding (6 4/6 fm.) was cleared by a 49-foot drag. (Chart Secondary)
- b. A 41 foot sounding (6 5/6 fm.) in lat. 18° 21' 180 m., long. 64° 49' 270 m., was cleared by a 50 foot drag. The sounding is marked 0.K. in the record (22 23 B, vol. 2, page 19).
- c. The 4 1/2 fathom wire drag sounding about 250 meters south of Steven Cay should have been further developed since no clearance depth was obtained with the drag. If shoaler water exists here it might be a menace to boats going to the dock at Little Cruz Bay.
- d. The 6 1/2 fathom sounding at the mouth of Redhook Bay in lat. 18° 19' 1700 m., long. 64° 50' 730 m. should be further developed. This bay forms a good refuge for small boats during a westerly blow.
- e. The passage between Little St. James and Great St. James Islands should have been developed. This appears to be a good passage for larger boats running between St. Thomas and Pillsbury Sound.
- f. About 3/4 mile south of Capella Islands the drag party obtained three soundings of 11 and 12 fathoms. There is a clear indication of a bank existing here, but very few soundings were taken by the hydrographic party. While the area has been covered to a safe depth for surface navigation, additional soundings are desirable to develop the full extent of this bank.
- g. Soundings should have been taken off Constant Point to at least develop the 5 fathom curve.
- h. Additional soundings should have been taken to the north of Frenchmans Cap. A 6 fathom sounding is now charted about 500 meters northwest of the Cap, which the present survey does not cover.
- i. In the vicinity of lat. 18° 17 1/2', long. 64° 43', an area about 3/4 mile square was left blank. This area was, however, dragged to a depth sufficient to insure that no navigational dangers exist.

- In attempting to account for positions 14 f and 17 f (vol. 11, j. pages 14 and 15) plotting on Flanagan Island it was found that O Leds and O Bad which were used in these fixes were erroneously plotted on the smooth sheet. @Leds was plotted about 30 meters to the eastward of its position as given on the original topographic sheet (T. 3783) and on the contemporary wire drag sheet (H. 4743b). OBad was plotted about 10 meters to the southward of its true position as given on the above two sheets. By using the correct positions of these two signals, the discrepancy was elminiated. It should be noted that numerous other positions were based on the use of the incorrect location of these two signals, but since it would have entailed a considerable amount of correction work to replot all the positions it was considered inadvisable to make the changes, particularly since no critical area is involved. For this reason the field plottings of the above two signals were retained on the sheet. A considerable amount of time was consumed by the writer in reconciling this discrepancy which properly should have been cleared up by the field party.
- About 150 meters south of Red Point, a bare rock was plotted on the smooth sheet by the field party. No authority could be found for this rock except the note in the sounding record at position 128 f (Vol. 11, page 28) "Rk on stbd side 5 m. away 2' water." There was 0.6 foot of tide at the time. Since the writer has personal knowledge of the conditions around this point, having made the topographic survey of this area, it is his belief that no such bare rock exists. So prominent a rock could not possibly have escaped notice during the progress of the careful and detailed shoreline delineation. The note was \This (4 therefore interpreted to mean that there was 2 feet of water corract. over the rock at the time of sounding and hence a 1/6 fathom See letter 128-1929. sounding will replace the bare rock on the smooth sheet.
- 1. The sunken rock shown on the smooth sheet in lat. 18° 21' 1640 m., long. 64° 46' 1320 m. should not be charted until further information is received from the field explaining how the rock came to be plotted on the sheet in the first instance. The descriptive report says the rock does not exist but the field party did not erase it from the sheet. It was covered by an 18 foot drag (H. 4743b.).
- 2. While practically all the indications of shoals have been adequately covered by the wire drag to insure that no dangers to surface navigation exist, yet from the viewpoint of physical hydrography there are several instances where development is lacking.

3. At the writing of this report the contemporary wire drag sheet H. 4743b covering this area had not yet been verified. When completed a detailed comparison will be possible as both surveys are on the same scale.

A. L. Shalowitz.

Approved:

Chief, Section of Field Records (Charts)

Chief, Section of Field Work (H. & T.)

Copy for Record Section files.

March 19, 1928.



Pivision of Hydrography and Popography:

Division of Charts:

Tide reducers are approved in volumes of sounding records for

HYDROGRAPHIC SHEET

47460

Locality: VIRGIN ISLANDS

Chief of Party: G. C. Mattison, 1925-4.

Plane of reference is K. I. Thomas

2.4 ft. on tide staff at I. Thomas

I. Thoma

Condition of records satisfactory except as checked below:

- 1. Locality and sublocality of survey omitted.
- 2. Month and day of month omitted.
- 3. Time meridian not given at beginning of day's work.
- 4. Time (whether A.M. or P.M.) not given at beginning of day's work.
- 5. Soundings (whether in feet or fathoms) not clearly shown in record.
- 6. Leadline correction entered in wrong column.
- 7. Field reductions entered in "Office" column.
- 8. Location of tide gauge not given at beginning of each day's work.
- 9. Leadline corrections not clearly stated.
- 10. Kind of sounding tube used not stated.
- 11. Sounding tube No. entered in column of "Soundings" instead of "Remarks".
- 12. Legibility of record could be improved.
- 13. Remarks.

Ellude

Chief, Division of Tides and Currents.

HYDROGRAPHIC SHEET No. - - - -

The following statistics will be submitted with the cartographer's report on the sheet:

Number of positions on sheet 7677

Number of positions checked 1475

Number of positions revised no account kept but no account kept but number of soundings revised not able to till

Number of soundings revised full a number due

Number of soundings revised full a number due

Number of signals erroneously

plotted or transferred none

Dato: August 16. 1928
Cartographor: John D. Jonney

U. S. COAST AND GEODETIC SURVEY

# HYDROGRAPHIC TITLE SHEET


The Hydrographic Sheet should be accompanied by this for filled in as completely as possible, when the sheet is for-	1,
warded to the Office.	0, & G. SURIVEY
Field No2	MAR' & 1928
REGISTER NO. 47438	Loc. No.
StateVIRGIN_ISLANDS	And the second
General locality ST. THOMAS AND ST. JOHN ISLANDS	-
Locality St. John Island and East end of St. Thomas, Island:	
Scale 1:20,000 Date of survey Sept.1923-Dec ,192	:
Vessel RANGER	<del>.</del>
Chief of Party G.C. Mattison	-
Surveyed by G.C.Mattison, C.K.Green, E.H.Bernstein, A.Ogrom, A.M. Lei	P.Ratti,
Protracted by JaMaBaker Jra	•
To the second se	
Soundings penciled by J.M.Baker Jr.	-
Soundings in <b>Sathbours</b> feet	-
Soundings in <b>faxbhows</b> feet	-
Soundings in <b>fathermst</b> feet  Plane of reference M.T.L. =0.5 ft.	
Soundings in <b>farbhows</b> feet  Plane of reference M.T.L0.5 ft.  Subdivision of wire dragged areas by	·
Soundings in <b>faxbhouss</b> feet  Plane of reference M.T.L0.5 ft.  Subdivision of wire dragged areas by  Inked by J. Z. Zoccey-	- - -
Soundings in factbrows: feet  Plane of reference M.T.L0.5 ft.  Subdivision of wire dragged areas by  Inked by J. T. Torrey-  Verified by J. Torrey	-

applied to Chart Comp. 938. January 1941. Williamswen

ļ. |-

.

# 47430 wo.



C. & G. SURVEY
L. & A
MAR 5 1928
Acc. No.

DEPARTMENT OF COMMERCE

COAST AND GEODETIC SURVEY

E. LESTER JONES, DIRECTOR.

VIRGIN ISLANDS

A DESCRIPTIVE REPORT to accompany

WIRE DRAG SHEET # 2 4743

1924-1927

S.S. RANGER

G.C.MATTISON,
H. & G. E.
C.K. Green, H. & G. E.
Chief of Party.

### DESCRIPTIVE REPORT

to accompany

WIRE DRAG SHEET #2

Original instructions dated June 22,1923.

## LIMITS OF SHEET:

Wire drag sheet #2 includes St.John Island and the East end of St.Thomas Island and waters surrounding. The limits are the same as for Hydrographic Sheet #2. The sheet extends between the limits of meridians 64° 37° and 64° 56° and the parallels 18° 13° and 18° 26°.

## METHODS:

All dragging was done using the launches MARINDIN and MITCHELL as guide and end launches respectively, and launch EDNA M, as a tender. Dual control methods were used throughout. Drag lengths varied from 1500 to 8400 feet. The personnel of the drag party was as follows. Guide launch; two officers, an engineer, a coxswain and two seamen. End launch; two officers, an engineer, a coxswain and one seaman. The soundings were taken from the tender with a sounding wire to which no correction was necessary.

## DRAG DEPTHS:

In general deep areas were dragged to 100 feet. Areas between 100 feet and 50 feet in depth were dragged to within ten feet of the bottom and areas less than fifty feet in depth within three feet of the bottom. These depths were altered considerably by the lift in the drag. Shoals were covered within three feet of the bottom where practicable. Dragging was carried as close inshore as practicable without causing too much delay due to grounding.

#### LIFT IN DRAG:

Previous to 1926 no allowances were made for lift in the drag. Previous to M\* day no tests were made for lift.

C.K. Green, H. & C. Engineer, while in charge of the drag party working in the Virgin Islands conducted a series of tests under various conditions of depth, speed, wind and currents and these results were tabulated and used as a basis for lift previous to the time regular tests were made, and used in conjunction with drag tests later. A copy of these tabulations is attached to this report.

End lift was found to be in excess of lift throughout drag. This was remedied by setting ends of drag deeper. It was also found that short bridles and towlines caused excessive end lift and consequently they were lengthened.

Additional corrections were made to allow for probable lift due to swell and chappy seas.

### RECORDS:

Rough tender records were used for sheets two and three, combined. Smooth records however were kept separate. Work on sheet three that was found in sheet two records has been copied into proper record.

## ADDITIONAL WORK:

After work was completed on sheet the insufficient overlaps, splits and places not properly dragged were noted and later the important splits etc were covered. This additional work was done between March 1 and March 21,1927 inclusive. Instructions from the Director dated February 28,1927 called for the omission of work in all except important areas.

## DEPTHS IN CHANNELS:

Thannel to maximum of 49 feet established between Buck Island and St. Thomas Island.

Channel of 47 feet south entrance to Pillsbury Sound extending thru Sound and out thru Middle Passage, on North side between Thatch and Grass Cays. Channels between Thatch Cay and St. Thomas Island, shown as Leeward Passage to depth of 41 feet.

A channel of 38 feet extends thru the Windward Passage into Pillsbury Sound.

A 49 foot channel was dragged thru the Narrows between Great Thatch Island and St.John Island. And a 41 foot channel was carried thru to Flannagan Passage.

A 28 foot drag was carried thru the passage between Leduck Island and St.John Igland.

A channel of 47 feet extends thru pass between Flannagan Island and St. John close to Flannagan Island. And a matter of 41 feet extends thru entire passage.

## PLOTTING:

On A day drag grounded at position six set at 50 feet. No sounding was obtained. Number one hucy was submerged, so evidently drag grounded below depth. Later covered by 50 foot drag.

On B day a drag of 55 feet grounded at position 11 and boat sheet location of 59 foot sounding was used. Location of shoal recorded in tender record would not plot. Later, on same day adrag set at 53 feet

hung up, at same place (depth reduced to 48 feet). At position 22 C''' a 57 foot drag grounded on same shoal and a 54 foot sounding was obtained. On D''' the shoal was covered with a 49 foot drag.

On D day a line was ended at position 11 because launches failed to take position while reversing to allow hookup. Split west was covered on J\*\*\* day.

At 19 K, drag grounded while set at 46 feet. Sounding of 60 feet was obtained. Several fish traps were caught on drag, probably  $\nu$  causing it to ground below depth. The spot was covered to 54 feet on D''' day.

On E' day drag grounded at position 18. Tender position plots ground ahead of drag. The boat sheet location of ground was used as that cheeks cuts from launches and bight of drag.

On F' day guide launch positions 15 and 16 were taken from the boat sheet to avoid sunning 34 minutes without a position.

Drag touched bottom in a number of places. Notations were penciled on sheet at places and they were also indicated in records.

Drag grounded on ridge between St.John and Tortola in several places and soundings found were greater than effective drag depth. No attempt was made to cover these soundings within three feet of the bottom as soundings verify the chart.

On X. day positions 1 to 8, path of far buoy, has been plotted using 70 meters towline instead of 40 meters. This has not been corrected.

On K day positions 1 to 21, path of far buoy has been plotted with 100 meter towline instead of 70 meters. This has not been corrected.

On F° day t throughout day) path of far buoy has been plotted with 125 meter towline instead of 100 meters. This has not been corrected.

## CURRENTS:

Greatest currents were found in Pillsbury Sound. During ebb tide, current flows to northward and during flood tide to the southward. A current of from one to four knots flows thru the Middle Passage and the Windward Passage on the north. Currents thru the Leeward Passage are less pronounced. At the south entrance to the Sound currents flow from one to four knots ans are strongest near Dog Island. The current lags with the tide from one half to three quarters of an hour.

Between Buck Island and St. Thomas, the current is barely perceptible.

A current attaining a maximum speed of from one to two knots flows between Flannagan Island and St.John Island.

In the Narrows, judging by speed of drag, current flows at a moderate speed.

## LANDMARKS:

Triangulation station GOV on a little peninsula in Little Cruz Bay, St.John Island, is a white massive stone structure, used as a givernment house for St.John and is so mamed. It is visible practically throughout the Sound.

In Francis Bay on highest part of America Hill is a large square Red House with a peaked roof that is visible along north of Cays on north side of Sound. It's location is the same as triangulation station AMERICA.

## ADDITIONAL REMARKS:

The work from February 2,1924 to November 25,1924 and from May 18,1925 to March 21,1927 was in charge of G.C.Mattison, H. & G. Engineer, as Chief of Party. The work from February 16,1925 to April 29,1925 was in charge of C.K.Green, H. & G. Engineer, as Chief of Party.

## GENERAL DESCRIPTION OF COAST:

There is nothing to be added to General Description of Coast as given in the present Coast Pilot.

# ANCHORAGES:

Anchorages are sufficiently described in the Coast Pilot except that several shoaler soundings were obtained, that limited some of the anchorages. These soundings are found under List of Shoals.

## COMPARISON WITH CHART:

The drag work as a whole serifies the chart.

A 34 foot drag on H''' day carried up against the west side of Steven Cay disproves four fathom sounding charted and marked P.D.

On shoal west of Hans Lollick Island, having charted depth of nine fathoms a sounding of 7-3/4 fathoms was found. Lat. 18 23' - 1297 meters, Long. 64 51' - 1513 meters.

A depth of 25.5 feet was found west of Leduck Island in Lat. 18 19° - 359, meters, Long. 65 41° - 1026 meters. No sounding charted. Least water charted in charmel; seven fathoms.

# SHORELINE:

Forwarded Gomettisa Edg. S. S. Ranger.

The shoreline for the English Islands was taken from bromides of Admirality charts. The correctness of it's location is questionable. Some of these are shown by full lines. They should all be shown by dash lines.

Respectfully submitted.

A.C. THORSON,

Jr. H. & G. Engineer.

## LIST OF SOUNDINGS:

A depth of 8.6 was found 745 meters 115° true from Green Cay in Lat. 18 18° - 996 meters, Long. 64 54° - 254 meters. Coral.

A depth of 34.5 feet was found 1449 meters, 99° true from Green Cay in Lat. 18 18° 1100 meters, Long. 64 53° - 1256 meters. A sounding of 35.5 feet was found on same shoal 28 meters S.E. of first sounding.

A depth of 5.6 feet was found on Packet Rock 1400 meters 252° true from Long Point in Lat. 18 18° - 74 meters, Long. 64 53° - 866 meters. Shoal is marked by a red nun buoy. Depth charted one half fathom.

A depth of 43 feet was found 1220 meters 245° true from Long Point in Lat. 18 17° - 1841 meters, Long. 64 53° - 649 meters.

Perted drag depth 57' Reg.

A depth of 58 feet was found 1638 meters, 245° true from Long-Point in Lat. 18 17° 1678 meters, Long. 64 53° - 1027 meters. Coral head.

A depth of 56 feet was found 1394 meters, 219° true from Long Point in Lat. 18 17° - 1270 meters, Long. 64 53° - 425 meters. Coral shoal.

A depth of 62 feet was found 683 meters 100 true from Buck Island Lighthouse in Lat. 18 17 - 320 meters, Long. 64 53 895 meters.

A depth of 42 feet was found 388 meters 327° true from Buck sland Lighthouse in Lat. 18 16' - 1821 meters, Long. 64 53' - 1227 meters.

A depth of 48 feet was found 498 meters 27° true from Buck Island Lighthouse in Lat. 18 17' - 93 meters, Long. 64 53' -792 meters. A depth of 52 feet was found 75 meters NW of 48 foot spot and a sounding of 54 feet was obtained 52 meters SE of 48 foot spot.

A depth of 44 feet was found 265 meters 10° true from Buck Island Lighthouse in Lat. 18 16° - 1753 meters, Long. 64655°- 967 meters.

A depth of 74 feet was found 1400 meters 1660 strue from Buck Island Lighthouse in Lat. 18 16\* - 25 meters, Long. 64 53\* - 671 meters.

A depth of 69 feet was found 1616 meters 1530 true from Buck Island Lighthouse in Lat. 18 16 - 48 meters, Long. 64 53 - 298 meters.

A depth of 74 feet was found 1510 meters 1870 true from Buck Island Lighthouse in Lat. 18 15' - 1677meters, Long. 64 53' - 1235 meters.

A depth of 59 feet was found 1709 meters 1910 true from Long Point in Lat. 18 17 - 665 meters, Long. 64 52 - 3632 meters, Long cral branches.

A depth of 61 feet was found 1582 meters 190° true from Long-Point in Lat. 18 17° - 791 meters, Long. 64 52° - 1582 meters.

A depth of 60 feet was found 1439 meters, 179° true from Long Point in Lat. 18 17° - 917 meters, Long. 64 52° - 1289 meters.

A depth of 57 feet was found 1005 meters, 181-1/2° true from Long Point in Lat. 18 17° - 1173 meters, Long. 64 52° - 1442 meters. Small coral head.

A depth of 27 feet was found 592 meters, 1020 true from Long Point in Lat. 18 18' - 580 meters, Long. 64 52' - 725 meters. A depth of 28 feet was found 492 meters 1060 true from Long Point near previous sounding in Lat. 18 18' - 360 meters, Long. 64 52' - 829 meters.

A depth of 26 feet was found 1092 meters 940 true from Middle / Rotto Cay in Lat. 18 18 - 1635 meters, Long. 64 51 - 515 meters.

A depth of 27.5 feet was found 1823 meters 1110 true from Middle of Rotto Cay in Lat. 18 18' - 1416 meters, Long. 64 51' - 793 meters.

A depth of 27.5 feet was found 672 meters, 215 true from Deck Point in Lat. 18 18' - 358 meters, Long. 64-50; - 1738 meters.

Coral head.

A depth of 23.5 feet was found 383 meters 171° true from Deck Point in Lat. 18 18' 1128 meters, Long. 64 50' - 1283 meters.

A depth of 51.5 feet was found 391 meters 148° true from Deck Point in Lat. 18 18° - 1180 meters, Long. 64 50° - 1134 meters.

A depth of 57 feet was found 1.6 miles 175° true from Cow / Rock in Lat. 18 16° - 1380 meters Long. 64 50° - 1313 meters.

A depth of 57 feet was found 1.502 miles 2270 true from / East End of Dog Island in Lat. 18 16' - 1544 meters, Lonh. 64 50' - 61 meters.

A depth of 56 feet was found 1893 meters 2640 true from East End of Dog Island in Lat. 18 17' - 1382 meters, Long, 64 49' p 1683 meters.

A depth of 59 feet was found 942 meters 2170 true from East End of Dog Island in Lat. 18 17' - 804 meters Long. 64 49' - 367 meters.

A depth of 57 feet was found 973 meters 2020 true from E. end of Dog Island in Lat. 18 17, - 669 meters Long. 64 49, - 165 meters.

A depth of 52 feet was found 1116 feeters 2070 true from E. end of Dog Island in Lat. 18 17' - 573 meters, Long. 64 49' -303 meters.

- plotted drag defath 48ft.

A depth of 54 feet was found 1370 meters 2130 true from E. end of Dog Island in Lat. 18 12: - 54 49 - 422 meters, Long. 64 49 547 meters.

A depth of 54 feet was found 1.382 miles 225° true from E. end of Dog Island in Lat. 18 16' - 1627 meters, Long. 64 49' - 1627 meters. A depth of 55 feet was found 85 meters S.E. of previous sounding on same shoal, 1.375 miles 223-1/2° true from E. end of Dog Island in Lat. 18 16' - 1579 meters, Long. 64 49' - 1551 meters. Large coral shoal.

A depth of 89 feet was found 3.223 miles 195-1/20 true from E. end of Dog Island in Lat. 18 14' - 1382 meters, Long. 64 49' - 1395 meters.

A depth of 54 feet was found 1155 meters 1870 tree from E. end of Dog Island in Lat. 18 17, - 426 meters, Long. 64 48 - 1704 meters.

A depth of 61 feet was found 1438meters 1110 from from E. end of Dog Island in Lat. 18 17' - 1057 meters, Long. 64 48' - 212 meters. Small shoal.

A depth of 46 feet was found 650 meters 73° true from E. end of Dog Island in Lat. 18 17' - 1763 meters, Long. 64 48' 938 meters. On same shoal a depth of 49 feet was found 650 meters 68° true from E. end of Dog Island in Lat.18 17' - 1822 meters, Long. 64 48' 951 meters. Also a depth of 53 feetwas found 670 meters 65° true from E. end of Dog Island in Lat. 18 18' - 8 meters, Long. 64 48' - 955 meters.

A depth of 54 feet was found 1.2 miles 1790 true from south end of Steven Hay Cay in Lat. 18 18' - 1178 meters. Long. 64 48' 748 meters. Another sounding of 59 feet was found 75 meters northwest of 54 foot depth was taken from boat sheet. Plotted drag depth 48 ft.

A depth of 24.5 feet was found 1085 meters 1120 true from Caborta Point in Lat. 18 198 - 724 meters, Long. 64 499 - 665 meters.

A depth of 29.5 feet was found 1232 meters 1150 true from Cabute Point in Lat. 18 19' - 601 meters Long. 64 49' - 508 meters.

A depth of 29 feet was found 1216 meters 1050 true from and has been fasted Cabate Point in Lat. 18 19' - 801 meters, Long. 64 49' - 462 meters. L. by 49 fr - Sky Branch coral.

A depth of 34 feet was found 477 meters 305° true from south end of Steven Way Cay in Lat. 18 19'- 1824 meters 64 48' - 1160 meters.

49 ft str

A depth of 34 feet was found 235 meters 275° true from south end of Steven May Cay in Lat. 18 19' - 1560 meters, Long. 64 48' 1010 meters.

A depth of 29.5 feet was found 210 meters 226° true from southern end of Steven May Cay in Lat. 18 19' - 1404 meters, Long. 64 48' 936 meters.

A depth of 27.5 feet was found 280, meters 182° true from southern end of Steven May Cay in Lat. 18 19' - 1268 meters, Long. 64 48' 783 meters.

A depth of 33 feet was found 661 meters 135° true from southern end of Steven May Cay in Lat.18 19' - 1076 meters, Long. 64 48' 312 meters. On same shoal 57 meters SSE of 33 foot depth and 714 metera 136° true from southern end of Steven May Cay depth of 24 feet was found in Lat. 18 19' - 1026 meters Long. 64 48' - 282 meters.

A depth of 20 feet was found 670 meters 76° true from southern end of Steven May Cay in Lat. 18 19' - 1700 meters and Long 64 48' - 126 meters.

A depth of 29 feet was found 286 meters 45° true from Brother Rock in Lat. 18 20°. - 1466 meters Long. 64 48° - 1654 meters.

A depth of 28 feet was found 542 meters 201° true from Lind Point in Lat. 18 20° - 74 meters, Lang. 64 48° - 135 meters.

A depth of 69 feet was found 734 meters 218% true from Bahvun Point in Lat. 18 18' - 827 meters Long. 64 47' - 511 meters. Shoal area about 10 meters.

plotted drag depth 53gt.

A depth of 59 feet was found 899 meters 213° true from Buhwan Point in Lat. 18 18' - 655 meters, Long. 64 47' - 352 meters.

A depth of 60 feet was found 1170 meters 2160 true from Buhvun Point in Lat. 18 18' - 460 meters Long. 64 47' - 548 meters.

A depth of 58 feet was found 1.107 miles 220-1/2° from Buhvun Point in Lat. 18 1%' - 1710 meters, Long. 64 47' - 1180 meters.

A depth of 62 feet was found 1.295 miles 2210 true from Buhvun Point in Lat. 18 17' - 1442 meters, Long. 64 47' - 1472 meters.

A depth of 79 feet was found 2.27miles 188° true from Ditlef Point in Lat. 18 16' - 970 meters, Long. 64 46' - 585 meters.

A depth of 24.5feet was found 937 meters 72° true from Ditlef Point in Lat. 1818' - 1696 meters, Long. 64 45' - 840 meters.

A depth of 92 feet was found 4.0 miles 1720 true from Ditlef Point in Lat. 18 14' - 1537 meters, Long. 64 45' - 671meters.

A depth of 102 feet was found 4.18 miles 180° true from Ditlef Point in Lat. 18 14° - 1083 meters. Long. 64 45° - 1726 meters.

A depth of 28.5 feet was found 955 meters 277° true from White Point in Lat. 18 19' - 60 meters Long. 64 44' - 872 meters.

A depth of 85 feet was found 2.726 miles 184° true from White Point in Lat. 18 16' - 441 meters, Long. 64 44' - 260 meters.

A depth of 77nfeet was found 1.602 miles 1210 true from L Ram Head Point in Lat. 18 17: 375 meters Long. 64 40: - 1351 meters.

A depth of 11 feet was found on north end of Eagle Shoal 916 meters 1990 true from South End of Leduck Island in Lat. 18 18. 976 meters, Long. 64 41. - 840 meters Coral shoal.

A depth of 25.5 feet was found 192 meters 315° true from West End of Leduck Island in Lat. 18 19' - 359 meters Long.64 41' -1026 meters. Coral shoal.

A depth of 30 feet was found 588 meters 32° true from north end of Leduck Island in Lat. 18 19° - 830 meters, Long. 64 41° 342 meters. Another sounding of 36 geet was found 40 meters south by east of 30 feet depth. Coral Head on coral shoal.

A depth 6f, 14 feet was 426 meter 5180 true from Lagoon Point in Lat. 18 20' - 223 meters, Long. 64 42° 360 meters.

A depth of 14 feet was found 751 meters 313° true from Lagoon Point in Lat. 18 20° 414 meters, Long. 64 42° - 608 meters, A sounding of 15.4 feet was found due east of 14 foot spot, distance 40 meters.

A depth of 22 feet was found 1003 meters 2390 true from Lagoon Point in Lat. 18 20° - 846 meters, Long. 64 42° 424 meters. Coral shoal.

A sounding of 19 feet was found 801° true from Turner \_\_\_\_\_\_\_ Point in Lat. 18 20' - 1434 meters, Long. 64 42' 161 meters.

A sounding of 15.5 feet was found 455 meters 112° true from Long Point in Lat. 18 21' - 213 meters, Long. 64 41' - 1202 meters. Coral head.

A sounding of 25 feet was found 677 meters 182° true from Long Point in Lat. 18 20° - 15 11 meters Long. 64 41° 1739 meters. Coral shoak.

A sounding of 30 feet was found 292 meters 3060 true from Turners Point in Lat. 18 200 - 1034 meters Long. 64 410 - 1220 meters. A sounding of 44 feet was found 40 meters north af and a sounding of 65 feet 52 meters south of 30 foot sounding indicate a small shoal.

A sounding of 33 Reet was found 66/meters 170° true from Turners Point in Lat. 18 20° - 207 meters Long. 64 41° - 870 meters.

A sounding on same shoal of 30.5 feet was found 626 meters 162 true from Turners Point in Lat. 18 20' - 264 meters, Long. 64 41' - 787 meters.

A sounding of 21 feet was found 500 meters 171° true from Turners Pojnt in Lat. 18 239 - 363 meters, Long. 64 41' - 895 meters.

A sounding of 19 feet was found 406 meters 1450 true from Turners Point in Lat. 18 20 523 meters Leng. 64 41 - 752 meters. On same shoal a sounding of 22 feet was found 466 meters 1360 true from Turners Point in Lat. 18 20 - 527 meters, Long. 64 41 -655 meters. These soundings are all on a coral shoal. Soundings on coral heads.

A sounding of 23 feet was found 838 meters 75° true from Turners Point in Lat. 18 20° - 1082 meters, Long. 64 41° 179 meters.

A sounding of 14 feet was found 612 meters 3190 from Moors Point in Lat. 18 120- 542 meters, Long. 64 40° - 1700 meters. Sounding on coral head. On same shoal 92 meters to the northwest a 21 foot sounding was found in Lat. 18 20° - 592 meters Long. HEEXMEXER 64 40° - 1623 meters. This sounding also on a coral head.

A depth of 42 feet was found 130 meters 105° true from Privateer Point in Lat. 18 20° - 252 meters Long. 64 39° -1212 meters.

Several drag strips were completed by dragging up against the west and north sides of Flannigan Island. In these cases the drag was grounded thru out its length and positions to locate bight were taken by tender together with soundings at these positions. Depths of 41 feet to 52 feet were recorded.

A sounding of 42 feet was found 1.80/miles 40° true from East End. of 25 ohn So.

A sounding of 42 feetbwas found north of St.John Island in Lat. 18 22° - 1009 meters, Long. 64 40° - 1174 meters. On same ridge a sounding of 47 feet was recorded in Lat. 18 22° - and 747 meters, Long. 64 41° - 323 meters. A depth of 45 feet was recorded in Lat. 18 22° 1203 meters, Long. 64 41° - 1080 meters. Another sounding of 49 feet was hocated in Lat. 18 22° - 257 meters, Long. 64 41° - 445 meters. A spunding of 45 feet was found in Lat. 10 22° -x1203 meters, Long. 64 41° 1065 meters. These soundingd were along a charted ridge between St.John and Tortola.

A sounding of 35 feet was recorded in Lat. 18 22\* -1054 meters, Long. 64 44\* 868 meters, in the Narrows.

In Francis Bay a shoal begins 600 meters due, south of the west end of Whistling and extends south west for a distance of 300 meters. A sounding of 17.5 feet was found 695 meters 1850 true from east end of Whistling Cay. A depth of 19.5 feet was found 85 meters north west of 17.5 feet spot and another sounding of 18 feet was recorded 152 meters to the south west of 17.5 foot sounding.

A depth of 12.7 feet was found 480 meters 32° true from north end of Trunk Cay in Lat. 18 21' - 125 meters, Long. 64 46° 13 m. Another sounding of 14.7 meters was found 168 meters SE from 12.7 foot spot.

A large coral reef known as Johnson Reef, a part of which is always awash has its center on a line between Hognest Point and the west end of Whistling Cay at a distance of 1420 meters, from Hognest Point. The reef is more or less circular in these and is about 500 meters agross/ A depth of 19 feet was found en edge of reef 1760 meters, 500 true from Hognest Point. Another sounding of 26 feet 1702 meters 440 from Hognest Point. A sounding on a coral of 10.7 feet was found 1483 meters 470 true from Hognest Point and a sounding of 24.5 feet was found 1310 meters 320 true from Hognest Point. Drag strips were ended by grounding drag through out onnreef and positions were taken innthe bight with soundings. These soundings run from nine seven feet to nine-teen five feet.

A depth of 33.5 feet was recorded south west of Durloe — Cay in Lat. 18 21° - \$20 meters Long. 64 47° - 1337 meters. A sounding of 36 feet was found south of Durloe Cay in Lat. 18 21° - 230 meters, Long. 64 47° - 1300 meters.

A depth of 20 feet was recorded 85 meters 150 true from Ratta Cay.

A sounding of 24 feet was found north of Durloe Cay in Lat. 18 21° - 1036 meters Long. 64 47° - 941 meters. A depth of 35 feet was found 30 meters South by East of 24 feet depth and a depth of 18.5 feet 103 meters south 65 24 foot spot. 18 flot in same for a 24% meters.

A depth of 38 feet was recorded north of the west end of Lovango Cay in Lat. 18 21' - 1771 meters and Long. 64 48' - 1358 meters.

475 The drag grounded at 50 feet south of Grass Cay in Lat. 18 21' - 370 meters Long. 64 49' - 1489 meters.

A depth of 42 feet was recorded south of Grass Cay 4 H day and later a depth of 35 feet was found on same shoal in Lat. 18 21 360 meters Long. 64 50' - 438 meters.

A depth of 23.5 feet was found 815 meters 305° true from Coke Point in Lat. 18 21 - 628 meters, Long. 64 52° - 30° meters. A sounding of 27.5 feet was recorded 20 meters south of first sounding. A depth of 42 feet was also recorded on this shoal.

A sounding of 49 feet was found 226 meters 90 true from West Point, Thatch Cay.

A sounding of 47 feet was found 20° true from West Point Great Thatch Cay, 477 meters distant.

A sounding of 47 feet was found 200 true from West Point Thatch Cay in Lat. 18 23' - 1297 meters, Long. 64 51' - 1513 meters.

A 23 foot sounding was recorded 1165 meters 279° true from West Point Thatch Cay in Lat. 18 21° - 1591 meters, Long. 64 53° -432 meters. Sounding on coral shoal.

A depth of 65 feet was recorded 1736 meters 1570 true from South end of Hans Lollick Island. On bearing of 1580 true a sounding of 62 feet was recorded 204 meters from 65 foot sounding.

A sounding of 78 feet was recorded south east of Hans Lollick Island in Lat. 18 23 - 1656 meters; Long. 64 53' - 686 meters.

A sounding of 42 feet was found on a shoal south east of Hans Lollick Island in Lat. 18 23' 9 335 meters, Long. 64 53' - 963 meters. Soundings of 45, 52 and 66 feet was recorded on same shoal.

A depth of 39 feet was recorded near Hans Lollick Rock 775 meters 1150 true from Hans Lollick Island. A sounding of 50 feet was recorded 170 meters south of the 39 foot spot.

STATISTICS
Wire Drag Sheet #2

Date	Let.	Vol.	Drag	Posi <b>š</b> ions	Miles	Soundings.
<u> </u>			length		stat.	
2-5-24	A	1	3000	32	2.0	•
2-6-24	В	1	3000	21	2.5	2
2-7-24	C	1	3000	<b>3</b> 5	6.3	2
2-8-24	D	1	2500	18	2.5	2
2-13-24	E	1	4200	36	6.5	
2-14-24	F	1	3000	13	2.0	
2-18-24	Ğ	ī	3200	23	5.0	2
2-19-24	H	1&2	3000	36	6.7	
2-20-24	J	2	1500	32	6.0	1 .
?-21-24	K	2	3600	28	7.5	1
∠ <del>0</del> –27–24	L	2	5000	34	7.3	
10-28-24	M	2	5000	31	6.0	<b>.</b>
10-20-24	n	2	6000	36	<b>8.</b> 0	1
10-29-24	P	2	6000	31	7.0	1
	Q.	2	6000	<b>3</b> 9	7.5	-
10-31-24 11-3-24	R.	2&3	6000	31	7.0	·
11-7-24	S	3	4000	63	6.0	2
	T.	3	3000	15	2.0	ī
11-10-24	Ŭ	3	4000	27	3.5	2
11-11-24	<b>A</b>	3	4000	33	6.0	2
11-12-24	M.	3 3	4000	<b>4</b> 8	8.5	2
11-1 <b>3</b> -24		3	4000	29	7.0	
11-14-24	X	3	8400	17	4.0	
11-17-24	Y Z		3200	41	5.0	6
11-18-24		3 4	2100	63	9.0	4
11-19-24	A *			42	8.0	5
11-20-24	B*	4	2800	24	5.5	
11-21-24	C'	4	5500	24	5.5	•
11-24-24	$\mathtt{D}^{\bullet}$	4	6000	18	4.0	2
			1800	55	7.0	2
11-25-24	E*	4	1500	21	3.5	~
2-16-25	F*	4	6000		3.5	1
2-17-25	G*	4	6000	29		1
2-18-25	H.	5	6000	3	0.3 <b>5</b> .5	i
2-19-25	J'	5	6000	28		*
2-20-25	K*	5	6000	25	5.3	1
2-24-25	$\Gamma_{ullet}$	5	6 <b>8</b> 00	24	3.6 5.3	1
2-25-25	M.	5	6300	28	3.0	♣.
3- 2-25	N.	5	6000	2 <b>1</b> 32	5.4	
3- 4-25	P*	5	6000			
3- 5-25	୍ଦ•	5	6000	. 22	2.0 7.0	<b>1</b>
3- 6-25	R.	5	6000	30		
3- 9-25	S†	5	6000	31	522	3 2
3-10-25	T •	6	4000	39 76	7.0	2
3 <del>1</del> 11-25	<b>U</b> *	6	4500	<b>36</b>	5.9	
3-12-25	γ.	6	3600	25	3.5	3
3-13-25	₩*	6	3600	24	3.3	4
3-16-25	X*	6	3600	18	2.3	1
3-17-25	A.	6	2400	20	3.0	2
3-18-25	Z T	6	2400			
			1500	19	2.5	2
3-19-25	A * *	6	3200	3 <del>4</del>	2.8	2
3-30-25	B**	7	2800	27	4.1	1

Statistics Wire Drag Sheet #2

Date	Let.	Vol.	Drag length	Pos.	Miles Stat.	Soundings.
4- 7-25	C11#	7	2100	17	3.0	1
4- 8-25	D++	7	2100	23	3.5	2
4- 9-25	E * *	7	2100	38	5.1	2
4-10-25	F* *	7	2100	17	3.2	1
4-13-25	G * *	7	2100	41	6.8	2
4-14-25	H••	7	2100	32	2.6	3
4-15-25	J::	7	2100	26	2.5	4
4-16-25	K++	8	2700	25	2.5	5
4-17-25	L**	8	2700	27	3.3	7
4-20-25	М	8	3200	30	5.2	ì
4-21-25	N • •	8	(3600	25	3.4	8
<del></del> ~1-~0	24	•	1600)	~0	***	
4-22-85	P**	8	4000	30	5.2	
4-23-25	Q**	8	4500	24	6.2	
4-24-25	Rit	8	7000	25	4.2	
4-27-25	S**	8	7000	25	5.8	
4-29-25	<b>т</b>	8	7000	26	6.3	
5-18-25	<u>υ••</u>	9	5000	22	3.5	1
5-20-25	<b>Ψ*</b> *	9	4500	10	1.2	6
5-21-25	M	9	4500 4500	17	2.4	2
5-22-25	" · ·	9	2000	8	1.6	3
6- 2-25	Υ,,	9	3200	J	1.0	Ū
0- 2-25	1	3	6300	29	4.3	1
6- 3-25	Z**	0	3200	29	1.0	î
	A * * *	9			0.5	•
6- 4-25		9	1600	6		
3- 1-27	B***	9	2400	20	3.4	_
3- 2-27	Ciii	9	4000	22	3.4	5
3- 3-27	D • • •	10	3200			
			3600	4		
			4000	43	6.9	2
3- 4-27	E	10	3000		<b></b> .	_
		• •	4000	49	7.0	3
3- 7-27	Fiit	10	3500	27	3.35	<b>X</b> 4
3- 8-27	G***	10	1500			
			1800		• •	
			2400	55	<b>5.</b> 6	13
3-9- 27	H'''	10	<b>1</b> 500			
			1800			
			3600	45	5.1	5
3-10-27	J'''	10&11	1500			
			1800			
	•		3200	30	5.2	5
3-11-27	Kiii	11	1600			
			3200	59	10.8	1
3-21-27	$\Gamma_{444}$	11	2800			
			2600	9	0.8	4
	Totals			2398	386.15	162

Total area dragged 137.8 square miles.

### TIDE DATA

Three tide staffs were established in Little Cruz Bay at different times for tides in Pillsbury Sound and vicinity,

Two staffs were established in Francis Bay for the area north of the sound except the area at the western edge of sheet around Hans Lollick Island which is referred to staffs in Magens Bay. Automatic tide gauges in St. Thomas Harbor used for areasouth of St. Thomas. One tide staff and one automatic portable tide gauge were maintained at different times in Coral Bay for the area on eastern part of sheet.

### ST. THOMAS TIDE GAUGES:

	Planemof reference Lowest tide observed Highest tide observed	M.T.L.	-0.5 ft.=	5.2 on staff. 4.9 " " 6.8 " "
MAGENS BAY TI	DE STAFF #1:			
	Plane of reference Lowest tide observed Highest tide observed	$M \cdot T \cdot L$	-0.5 ft=	5.93 pn staff. 5.4 " " 7.8 " "
MAGENS BAY ST	AFF #2:			
	Plane of reference Lowest tide observed Highest tide observed	M.T.L.	-0.5 ft=	1.5 " " 1.0 " " 2.7 " "
LITTLE CRUZ B	AY STAFF #1:			
	Plane of reference Lowest tide observed Highest ti <b>de o</b> vserved	M.T.L	-0.5 ft=	2.55 " " 2.5 " " 4.0 " " "
LITTLE CRUZ B	AY STAFF #2:			
	Plane of reference Lowest tide observed Highest tide observed	M.T.L.	-0.5 ft=	2.4 " " " 3.6 " "
LITTLE CRUZ B	AY STAFF #3:			
	Plane of reference Lowest tide observed Highest tide observed	M.T.L.	-0.5 ft=	1.2 " " " " " 2.2 " "
FRANCIS STAFF	#3:			
	Plane of reference Lowest tide observed Highest tide observed	M.T.K.	- <b>Ø</b> 05 ft.=	2.83 " " 2.1 " " 4.0 " "

## TIDE DATA #2.

## FRANCIS BAY STAFF #2

Plane of reference Lowest tide observed Highest tide observed	M.T.L.	<b>-</b> 0.5	ft.=	1.4 1.2 2.8	17	11	staff "
CORAL B AY STAFF #1							
Plane of reference	M.T.L.	-0.5	ft.=	1.45	, 11	17	ú
Lowest tide observed				1.2	17	**	11
Highest tide observed				2.8	11	17	¥¥
CORAL BAY STAFF #2							
Plane of reference	M.T.L.	-0.5	ft.=	1.6	11	ıŧ	H ,
Lowest tide observed				1.3	Ħ	11	11
Highest tide observed				2.1	77	19	11

#### LIST OF SIGNALS

Hydrographic signals on this sheets were located by sextant and theodolite cuts.

After searching thru all records, cuts to the following signals could not be located.

Hydro. signal SEE used for three positions.

" " GIT " " one "
" " PIK " " one "
" " two "
" " RON " " one "

Signals CON and VOU on Congo Cay are the same. VOU used to keep from confusing with signal CON on west side of St. John Island.

Signals FLAN and FLAM are the same. Triangulation station FLANNIGAN was not used in drag work.

Signals MOT and MAT on Thatch Cay are the same.

Name	L	at	DM	Lo	ng	DP	Remarks.
Top							Trian. TOP Frenchmans Cap
Buck							" Buck Id. Lighthouse.
Con	18	16	1089	64	53	1460	WW Located by cuts Hydro.
Pa <b>n</b>	18	16	1214	64	53	795	WW Rock " " " "
East							Frian. E.Point Lighthouse
Green							" Tripod High. part Green Cay
French							Topo. Peak Red Roofed House
Cuk-							Trian. WW on face of Bluff
Mid							Topo. W.W.
Long,	18	18	502	64	52	1300	W.W. on rocky point
Gas							Trian. Trapod top of Cas Cay
Rotto							Trian. Sig. Top of Rotto Cay
Cow							Topo. Isolated Rock
Calf							17 17 17
Rock	18	19	36	64	51	296	Hydro. Rock. Sex. and Theo. cuts Topo
Sea	18		00	64		39	W.W. Hydro. " " "
On	18		1619		50	1490	Hydro. W.W. " " " "
Deck					•		Triangulation
Pet	18	18	1658	64	50	1085	Hydro. Rock W.W." " "
Rat	18		1784	64		1165	" " Sextant cuts
Pass							Triangulation W.W. Rock
Shi	18	18	1353	64	49	1590	Hydro. W.W. Sextant cuts
Ize	18		1242	64		92	"rock " "
San	18		841	64	50	266	" W.W. " "
Saint	10	-0	<b>014</b>	<b>.</b>	•	~~~	Triangulation
Say	18	18	760	64	49	1385	Hydro. W.W. "
Mes	18		312	64		1343	Hydro. W.W. " "
James	10	10	01~	01	-	1010	Triangulation. Little St. James Is.
	18	מנ	1796	64	49	1201	Hydro. W.W. Semtant cuts
Dan	18		1693	64		635	Hydro. W.W. ""
Ned	TO	<b>1</b> 1	1030	0.7	<b>T</b> J	000	Triangulation W.W.
Dog	10	10	650	64	1Q	894	Hydro. W.W. sextant cuts.
Las	18	70	650	04	<del>- 2</del> 2	0.5-2	There a name a management and a

Name	Lat.	DM	Long	DP	R_marks.
Welk	130.00	1000	2012		Topo. rock
	18 18	1642	64 49	714	Hydro. sextant suts
Noe	10 10	TOIN	01 11	122	Topo. middle of rock
Bone					Triangulation W.W.
Car	30.30	3 7 0 0	C4 50	640	Hydro. W.W. Sextant cuts
Kag	18 19	1329	64 50	<b>64</b> 0	•
Jack	10.10	000	C4 53	EAE	Topo. Jack Rock
Zef	18 19	900	64 51	545	Hydro. Sextant cuts
Blank	18 20	325	64 51	723	Hydro. W. House. Sextant cuts
Shark					Triangulation Tripod
Low				3.68	Topo. Reg. mark
Cos	18 20	969	64 51	163	Hydro. Sextant and Theo. cuts.
Bet	18 20	1495	64 51	1307	• 41.13
Coki					Triangulation W.W.
Ro	18 21	316	<b>64</b> 52	314	Hydro. W.W. Sextant and Theo.cuts
Ben	18 21	450	64 52	702	Hydro. W.W. " " "
Fag	18 21	517	64 52	1186	Hydro. W.W. " " " "
Sun					Topo.
Dal					Topo. Top of Round Hill
Man					Topo. W.W.
Rough					Triangulation W.W.
Hans					11 11 11
Lollick					# ·
A'b <b>e</b>	18 23	1224	64 54	13	Hydro. WW Sext. madxThmm.cuts
Gro	18 23	1357	64 53	1739	Hydro. "" " "
Let	18 23	1624	64 54	133	Hydro. WW "
Las	18 24	<b>4</b> 59	64 54	565	11 1111 11 11
Steek	18 24	1343	64 54	336	11 11 11 11
My	18 24	1624	64 54	670	19 10 11 11
Pel	18 24	1832	64 54	1109	" "" Rock Sext. cuts
Lo	18 24	408	64 54	1742	n m th ii ii
West	10 21	200	0. 0.		Triangulation
Sou	18 21	1269	64 52	859	Hydro.WW. Sext. and Theo cuts
Stone	18 21	1233	64 52	398	m nukku u u u
Buff	18 21	1018	64 51	1323	19 1919 19 19 19 19
Hat	18 21	980	64 51	678	17 17 19 19 19 17 17
Blow	10 ~1	200	01 01	0.0	Triangulation W.W.
Side	18 21	1373	64 51	00	Hydra. WW Sext. cuts
Off	18 21	1631	64 51	<del>1651</del> 438	
	18 21	1360	64,51	1364 935	
Kee Tat	18 21	1425	64 51	1425 1720	
	18 21	1425 1649	64 52	1650 300	
Tom Wot	18 21	1699	64 52	447	Topo. WW
Mot		1099	64 50	560	Hydro. WW. Sextant cuts
On Barr	18 21		64 50 64 50	283	m mm m m
Run	18 21	1264			17 1777 17 17
Rup	18 21	1315	64 50	155	
Get				•	Topo. WW Rock
Mingo	10.03	1501	64 40	3454	Triangulation
Say	18 21	1526	64 48	1454	Hydro. WW Sextant cuts
Teg	18 21	1597	64 48	1347	
B <b>ro</b>	18 20	<b>1285</b> v	64 49	110	". Brother Rocks (Largest)
Go	18 21	1160	64 48	1090	" WW Sextant cuts
<b>M</b> ig	18 21	1728	64 48	635	77 <b>6937</b> 17 17
Lovango					Triangulation
Mard					Topo. Murder Rock
Blund					Торо
					Trian. Tripod Sta. Carval

Nam <b>e</b>	Lat.	DM	Long.	DP	Remarks
Pip	18 22	484	64 47	1563	Hydro. WW Sextant cuts
Vou	18 22	246	64 48	915	19 1919 19 19
Sel	18 21	758	64 47	623	17 17 19 <b>17</b>
Isle					Triangulation
Sle	18 21	580	64 47	1130	Hydro. Tree on Henley Cay
Hog			-		Topo. WW
Bit	18 21	246	6 <b>4 47</b>	154	Hydro. WW Hognest Point (Bowlder on s
Сазеу					Topo. WW From Topo sheet
Lind					Triangulation
30V					" Gable, Gov't House
Row	18 <b>29</b>	1626	64 47	1702	Hydro. From Boat sheet
Rain	18 19	1394	64 47	1554	Hydro. WW sextznt cuts
Purn	18 19	1304	64 48	2	Hyddo. "" "
Con	18 19	6 <b>8</b> 3	64 47	1226	11 11 11 11 Topo
Maria	<del>1</del>				Triangulation
Ria	18 18	1816	64 47	882	Hydro. WW Sextant cuts
Run	18 19	240	64 47	329	18 1811 11 18
Bluff	18 18	1818	64 47	535	तं संस्तं भा भा
Cat	18 18	1753	64 47	224	17 1917 17 17
Vic	18 18	1550	64 47	07	12 v211 tt 12
Rend					Triangulation
Bul					Triangulation
Don	18 1 <b>8</b>	1565	64 46	1414	Hydro. WW Sextant cuts
Boat	18 19	220	64 46	929	Hydro. WW " "
May					Triangulation
[f	18 19	494	64 46	437	Hydro. WW sextant cuts
Less	18 19	407	64 46	181	11 1119 11 19
20	18 19	183	64 46	70	17 11 17 17
rie	18 18	1539	64 46	204	11 11 11 17
Pin	18 18	1398	64 46	44	11 11 11 11
Vou	18 18	1420	64 46	6	10 11 10 17
Piz	18 19	397	64 45	1746	11 ° 11 ° 11 • 11
Fish					Topo. WW
(ap	18 19	201	64 45	717	Hydro. WW " "
Bay	18 19	645	64 45	239	Hydro. WW " "
See	18 19	998	64 45	24	" From boat sheet
Chim					Topo. Brick Chimney
Hit	18 19	303	64 44	642	Hydro. WW
Lam	<del></del>		<del></del>		Triangulation W.W.
ab Gab	18 19	248	64 43	1306	Hydro. WW Sextant cuts
Vip	18 19	99	64 43	1018	11 1111 11 11 1000
fox	18 18	1549	6443	686	12 14 17 19
30k	18 18	1122	64 43	619	" " ondetached rock
Brite		~~		~ <del>~~</del>	Triangulation
Rit	<b>1</b> 8 18	1064	64 43	360	Hydro. WW. Sextant cuts
Min	18x18				Triangulation Sta.Minnahill Peak
at	ARAAB				Topo. From topo. sheat
alt					11 11 11 11
ond					17 11 17 17
					" W.W.
Kid					
300					Triangulation Sta. Booby
lead		•			Topo. W.W.
Ram		500		40	Triangulation
Zip	18 18	582	64 42	49	Hydro. W.W. Sext. and Theo. Cuts
An					Triangulation Sta. Nanny
ab					Topo. WW.

Harry Control of the					_			<del> </del>
Tree   18 19	Name		Lat.	<b>DM</b>	L	ong.	DP	Remarks
Lag	Coral							Triangulation Tree on
Second   18   19   1798	Tree	18	19	214	64	.41	693	Hydro. Sextant and theo.muts/ Leduck)
Topo. W.W Topo. Frominent Rock Triangulation Tripod Topo. W.W Topo	Lag							Triangulation Sta. Lagoon WW
Topo. W.W  Tap 18 21 185 64 43 572 Hydro. Mill Sext. cuts & BS  Berg  Bor 18 20 976 64 42 790 Hydro. WW " "  Bat imre  Bil 18 20 1699 64 42 403 Hydro. WW " "  Mit 18 21 357 64 42 440 Hydro. WW " "  Mit 18 21 960 64 41 1751 Hydro. WW " "  Mit 18 21 960 64 41 1751 Hydro. WW " "  Mit 18 21 960 64 41 1751 Hydro. WW " "  Mit 18 21 960 64 41 1751 Hydro. WW on Rocky Point  Her  Big Topo. WW  Topo. WW  Topo. WW  Topo. WW  Topo. WW on Rocky Point  Triangulation WW  Topo. WW on Rocky Point  Triangulation Tripod.  Topo. WW  Topo. W	Goon	18	19	1798	64	42	569	Hydro. WW Sext. and Theo Cuts
Top. W.W Tap 18 21 185 54 43 572	<b>Pot</b>							<del>-</del>
Serg   Serg   Topo.   W   Topo.   W   Triangulation   Triang								<del></del>
Berg   Bor   18 20   976   64 42   790   Hydro. WW   "   "   Triangulation WW   Bt   18 21   357   64 42   440   Hydro. WW   Sextant outs   Triangulation WW   Triangulation Triangulation WW   Triangulation Triangulation WW   Triangulation Triangulation Triangulation Triangulation Triangulation Triangulation WW   Triangulation Triangulation WW   Triangulation Triangulation Triangulation WW   Triangulation Triangulation WW   Triangulation Triangulation WW   Triangulation Triangulation WW   Triangulation WW   Triangulation WW   Triangulation WW   Triangulatio	Tap	18	21	185	64	43	572	· ·
Bot   18 20   976   64 42   790	Us	18	20	1495	64	42	1210	44 MA 14 14
### Bat ####### ########################	Berg							- • · · ·
### 18 20	Bor	18	20	976	64	<b>4</b> 2	790	There's an
Top 18 21 357 64 42 440								-
Mut 18 21 950 64 41 1751 Hydro. SE Corner Old Ruins Her Her  Mid 8 Topo. WW Mid 7 Topo. WW Mid 8 Topo. WW on Rocky Point Hydro. WW on ruin Aextent cuts Topo. WW Topo								
Her								TACTO - MM
### Topo. WW on Rocky Point ### Topo. WW on Rocky Point ### Topo. WW on Rocky Point ### Topo. WW on ruin Aextent cuts ### Topo. WW on ruin Aextent cuts ### Topo. WW #### Topo. WW #### Topo. WW #### Topo. WW ###################################	Mit	18	21	960	64	41	1751	
Mid								
Tow 18 20 1817 64 41 1063 Hydro. Ww on ruin mextant cuts Topo Wr Turn 18 20 862 64 41 983 Rydro. Ww Sextant cuts Lim 18 20 1506 64 40 1760 " "" " Topo. Ww Topo. Prominent Rock Triangulation Tripod Bad Wat 18 20 458 64 40 110 Hydro. Ww. Sextant & Theo.cuts Pry Ledge Corn 18 20 1543 64 40 99 Hydro. Ww sextant cuts Rock 18 20 1573 64 40 99 Hydro. Rock " " 7000 New 18 21 1573 64 40 99 Hydro. Rock " " 7000 Pik 18 21 237 64 40 842 " " " " " New 18 21 237 64 40 842 " " " " " Ner 18 20 1806 64 40 1172 " " " " Triangulation Ww Plam (N) Ru 18 23 1251 64 38 1617 Hydro. Ruins on Tortola Rose Red 18 23 135 64 44 41 83 Hydro. Wr Sextant cuts Red 18 23 135 64 44 45 Hydro. From Red House Sext.cuts Red 18 23 146 64 45 15 Hydro. From Red House Sext.cuts Red 18 21 1473 64 41 834 Hydro. Wr Sextant cuts Triangulation Topo. Rea 18 21 1473 64 41 834 Hydro. Wr Sextant cuts Red 18 23 235 64 40 727 Hydro. Wr Sextant cuts Red 18 23 235 64 40 727 Hydro. Wr Sextant cuts Red 18 23 235 64 40 727 Hydro. Wr Sextant cuts Red 18 23 235 64 40 727 Hydro. Prominent Grey Bowlder Tartola Triangulation T	Big							
Pop   Turn		-						
Turn 18 20 862 64 41 983 Hydro. WW Sextant cuts  Ilm 18 20 1506 64 40 1760 " " " " "  Round  Pel  Moor Bad  Vat 18 20 458 64 40 110 Hydro. WW. Sextant & Theo.cuts  Triangulation Sta. Privateer WW  Topo. WW  Topo. WW. Sextant & Theo.cuts  Triangulation Sta. Privateer WW  Topo. WW  Corn 18 20 1543 64 40 99 Hydro. WW. Sextant cuts  Rock 18 20 1573 64 40 99 Hydro. Rock " " 7000  Pelk 18 21 99 64 40 288 Hydro. WW " "  Pelk 18 21 237 64 40 842 " " " " " "  Ver 18 20 1806 64 40 1172 " " " " "  Flam (N)  Ru 18 23 1251 64 38 1617 (Hydro. Ruins on Tortola  (Sextant and Theodolite cuts  Hydro. Tripode sextant cuts  Hydro. Tripode sextant cuts  (Hydro. Ruins on Tortola  (Sextant and Theodolite cuts  Hydro. Tripode sextant cuts  Hydro. Tripode sextant cuts  Flam (N)  Ru 18 23 135 64 44 \$15 Hydro. Trom Red House Sext.cuts  Fless  Bed 18 23 146 64 45 \$57 Hydro. Yellow Bluff of Great The tolk Isla  Topo.  Sea 18 21 1473 64 41 834 Hydro. WW Sextant cuts  Triangulation  Triangulation		18	20	1,617	64	41	1063	•
Lim					•			
Topo. WW  Pel Topo. Prominent Rock  Triangulation Tripod  Topo. WW  Vat 18 20 458 64 40 110 Hydro. WW. Sextant & Theo.cuts  Pry Total Rock Triangulation Sta. Privateer WW  Topo. WW  Corn 18 20 1343 64 59 1200 Hydro. WW sextant cuts  Rock 18 20 1543 64 40 99 Hydro. Rock " " 7000  New 18 21 237 64 40 842 " " " " "  Prik 18 21 237 64 40 842 " " " " "  Prik 18 21 237 64 40 842 " " " " "  Ver 18 20 1806 64 40 1172 " " " " "  Haul Tax28  Flam (N)  Ru 18 23 1251 64 38 1617 [Hydro. Ruins on Tortola (Sextant and Theodolite cuts  Red 18 23 146 64 45 157 Hydro. Yellow Bluff on Great Thatch Isla  Men  Sea 18 21 1473 64 41 834 Hydro. WW Sextant cuts  Pleas  Topo.  Sea 18 21 1473 64 41 834 Hydro. WW Sextant cuts  Pleas  Topo.  Sea 18 21 1568 64 42 999 690 Hydro. WW Sextant cuts  Triangulation  Triangulat								
Topo. Prominent Rock Triangulation Tripd Bad  Vat 18 20 458 64 40 110 Hydro. WW. Sextant & Theo.cuts Pry Tedge Corn 18 20 1343 64 59 1200 Hydro. WW sextant cuts Rock 18 20 1573 64 40 99 Hydro. Rock " " 7000 New 18 21 79 64 40 288 Hydro. WW " " Pik 18 21 237 64 40 842 " " " " " " " " " " " " " " " " " " "	_	18	20	1506	64	40	1760	
Moor Bad  Wat 18 20 458 64 40 110 Hydro. Ww. Sextant & Theo.cuts  Pry Triangulation Sta. Privateer WW Topo. WW  Corn 18 20 1343 64 59 1200 Hydro. Ww sextant cuts  Rock 18 20 1573 64 40 99 Hydro. Rock " " 7000  New 18 21 79 64 40 288 Hydro. WW " " "  Pik 18 21 237 64 40 842 " " " " " "  Wer 18 20 1806 64 40 1172 " " " " " "  Haul 1822  Flam (N)  Heaul 1823 1251 64 38 1617 [Hydro. Ruins on Tortola (Sextant and Theodolite cuts  Roce 18 23 135 64 44 515 Hydro. From Red House Sext.cuts  Fel 18 23 146 64 45 157 Hydro. From Red House Sext.cuts  Fleas 18 21 1473 64 41 834 Hydro. WW Sextant cuts  Triangulation WW  Flow 18 21 1588 64 42 999 690 Hydro. WW Sextant cuts  Triangulation							•	
Topo. WW   Sextant & Theo.cuts   Triangulation Sta. Privateer WW   Topo. WW								
Vat								
Triangulation Sta. Privateer WW   Topo. WW		• •		450			110	
Topo. WW		TR	20	458	04	40	110	
Corn 18 20 1343 64 59 1200 Hydro. WW sextant cuts  Rock 18 20 1573 64 40 99 Hydro. Rock " " 7000  New 18 21 79 64 40 288 Hydro. WW " "  Pik 18 21 237 64 40 842 " " " " "  Ver 18 20 1806 64 40 1172 " " " "  Haul 1822 Triangulation WW  Hydro. Tripode sextant cuts  Red 18 23 1251 64 38 1617 (Hydro. Ruins on Tortola (Sextant and Theodolite cuts  Red 18 23 146 64 45 157 Hydro. Yellow Bluff on Great Thetch Isla  Men 18 21 1473 64 41 834 Hydro. WW Sextant cuts  Topo.  Sea 18 21 1473 64 41 834 Hydro. WW Sextant cuts  Triangulation WW  Tow 18 21 1568 64 42 999 690 Hydro. WW Sextant cuts  Lein Triangulation								
Rock 18 20 1573 64 40 99 Hydro. Rock " " 700  New 18 21 79 64 40 288 Hydro. WW " " " Pik 18 21 237 64 40 642 " " " " " " " " " " " " " " " " " " "		•		3.57.5			1000	
New 18 21 79 64 40 288 Hydro. WW " " " " " " " " " " " " " " " " " "								
Pik 18 21 237 64 40 842 " " " " " " " " " " " " " " " " " " "								Hydro. Hook
18 20								TAGE MA
Triangulation   Topo   Topo   Triangulation   Topo   Topo   Topo   Triangulation   Topo   Topo   Topo   Triangulation   Topo   Triangulation   Topo   Topo   Triangulation   Topo								
Hydro. Tripode sextant cuts   Hydro. Ruins on Tortola   Sextant and Theodolite cuts   Sextant and Topo   Sextant cuts   Sextant and Triangulation   Sextant cuts   Sextant and Triangulation   Topo   Sextant and Triangulation   Topo			-	1809	64	40	1172	
18 23   1251   64 38   1617		XXX	CK M					
Sextant and Theodolite cuts   Seed   18 23   135   64 44   615   Hydro. from Red House Sext.cuts   Seed   18 23   146   64 45   157   Hydro. Yellow Bluff   Seed   Seed   18 21   1473   64 41   834   Hydro. WW Sextant cuts   Triangulation WW	-		0.7	3.053		<b>70</b>	3638	· ·
Red 18 23 135 64 44 615 Hydro. from Red House Sext.cuts  Yel 18 23 146 64 45 \$57 Hydro. Yellow Bluff on Great Thatch Isla  Men  Topo.  Sea 18 21 1473 64 41 834 Hydro. WW Sextant cuts  Pleas  Triangulation WW  Tow 18 21 1568 64 42 989 690 Hydro. WW Sextant cuts  Triangulation  Topo  Let 18 22 734 6-1-75 881 Hydro. WW Sextant cuts  Nie 18 22 519 64 45 645 ". W.Gable Ruin Whistling Cay		19	23	1251	54	96		
Topo		10	08	175	C A	4.4		
Sea								
Sea		19	20	140	04	45	101	Mone iellow Billi on Great Thatch Isla
Triangulation WW  Tow 18 21 1568 64 42 989 690 Hydro. WW Sextant cuts  Lein Triangulation  Need Triangulation		10	0.7	3 4 77 7	C A	43	074	- · · · · · · · · · · · · · · · · · · ·
Tow 18 21 1568 64 42 909 690 Hydro. WW Sextant cuts  Lein Triangulation  Need Triangulation  Triangulation  Bol 18 23 235 64 40 727 Hydro. Prominent Grey Bowlder Tartola  Berg Triangulation  Nar 18 22 853 64 44 955 963 Hydro. WW Sextant cuts Tope  Was 18 22 905 64 44 1709 " " " "  Mary Triangulation  Fin Tope  Let 18 22 734 6+75 881 Hydro. WW Sextant cuts  Nie 18 22 519 64 45 645 " W.Gable Ruin Whistling Cay		ΤQ	41	1475	04	41	094	
Triangulation  Triang		10	o <b>1</b>	1550	C A	4.9	000 600	
Triangulation   Triangulatio		TQ	ζŢ.	TO <b>P</b> O	04	46	محم همد	— <del>V</del>
Triangulation  Bol 18 23 235 64 40 727 Hydro. Prominent Grey Bowlder Tartola  Berg Triangulation  Anna Triangulation  Nar 18 22 853 64 44 955 963 Hydro. WW Sextant cuts Tope  Was 18 22 905 64 44 1709 " "" "  Mary Triangulation  Fin Tope  Let 18 22 734 6+75 881 Hydro. WW Sextant cuts  Nie 18 22 519 64 45 645 " W.Gable Ruin Whistling Cay				-				_
Bol 18 23 235 64 40 727 Hydro. Prominent Grey Bowlder Tartola Triangulation  Anna Triangulation  Nar 18 22 853 64 44 955 963 Hydro. WW Sextant cuts Topo  Was 18 22 905 64 44 1709 " " " " "  Wary  Triangulation  Topo  Let 18 22 734 6+45 881 Hydro. WW Sextant cuts  Nie 18 22 519 64 45 645 " W.Gable Ruin Whistling Cay								
Triangulation Triangulation Triangulation  Nar 18 22 853 64 44 955963 Hydro. WW Sextant cuts Tope Nas 18 22 905 64 44 1709 " " " "  Mary Triangulation Tope Let 18 22 734 6+45 881 Hydro. WW Sextant cuts Nie 18 22 519 64 45 645 " W.Gable Ruin Whistling Cay		3.0	25	246	e A	40	non	
Triangulation  Nar 18 22 853 64 44 955 963 Hydro. WW Sextant cuts Topo  Nas 18 22 905 64 44 1709 " " " "  Mary  Triangulation  Topo  Let 18 22 734 6+45 881 Hydro. WW Sextant cuts  Nie 18 22 519 64 45 645 " W.Gable Ruin Whistling Cay		TQ	20	೭೮೦	04	40	121	•
Nar 18 22 853 64 44 955 963 Hydro. WW Sextant cuts Topo  Was 18 22 905 64 44 1709 " " " "  Mary  Triangulation  Topo  Let 18 22 734 6+75 881 Hydro. WW Sextant cuts  Nie 18 22 519 64 45 645 " W.Gable Ruin Whistling Cay	_							
Was       18 22       905       64 44       1709       " "" " " " " " " " " " " " " " " " " "	-	3.0	00	055			05-55	
Triangulation Fin Topo  Let 18 22 734 6+45 881 Hydro. WW Sextant cuts Vie 18 22 519 64 45 645 "W.Gable Ruin Whistling Cay								
Topo  Let 18 22 734 6+45 881 Hydro. WW Sextant cuts  Nie 18 22 519 64 45 645 ". W.Gable Ruin Whistling Cay		18	22	905	<b>64</b>	44	1709	
Let 18 22 734 6+45 881 Hydro. WW Sextant cuts Nie 18 22 519 64 45 645 ". W. Geble Ruin Whistling Cay	-							
Wie 18 22 519 64 45 645 "W.Gable Ruin Whistling Cay								<del>-</del>
					6+	45	881	<del>-</del>
Wis	Nie	18	22	519	64	45	645	" W. Gable Ruin Whistling Cay
	Wis							Triangulation

Name		Lat.	DM .	L	ong.	DP	R <sup>E</sup> marks
	10	0.7	1383	£ A	44	1310 1210	Hydro. WW Sextant and Theo cuts
Мо		21			45	254	Hydro. WW SMerica Point
Rick	18	21	1088	04	40	204	Triangulation Sta.America
Am							· ·
							Gable of Red Roof House.
Cin							Triangulation on Cimnamon Cay
Pete	18	21	<b>79</b> 8	64	45	1417	Hydro. WW On Point Sext. cuts
Trunk	18	21	864	64	46	269	Hydro. WW Sext. cuts
Rag	18	21	409	64	46	417	Hydro. WW " "
Goo		21	600	64	46	799	19 1999 19 19
Perk							Triangulation Sta. Perkins
Sugar							TriangulationMill
Bal	10	21	118	64	46	1152	Topo. Conspicuous Rock

·

•

The weights used on the tests owere, large, 180 lbs. small, about 35 lbs. Metallic floats were used. Speeds, currents and winds are tabulated in knots. "Sea smooth" is tabulated when there was not enough swell to effect the drag. "Medium bight" is 85 to 90% effect; width, and "Taut bight" is 95%. The tests of the end sections were taken close to the large buoys.

- No. 1. Bight too taut; speed through the water slightly excessive.
- No. 3. Speed excessive for 40 foot end; if towline had been longer, lift at F would have been less.
- No. 4. 100 ft. bridle gives excessive lift at F; towline should have been the same as at N, which was 200 ft. briddle and 200 ft. straightaway. (See test No.5).
- No. 5. Note how lift extends overin the loo ft. sections, due to difference in hook ups at N and F.
- No. 6. Bight too slack, produces more lift in middle sections than in end sections.
- No. 7. Lift in 4th section due to differences in hook-ups of the ends, with taut bight.
- No. 8. Shows lift to be expected at this speed and depth.
- Nos. 9 to 13. Shows lift to be expected when dragging around 1.5 knots at a depth of 65 ft. Note that directions of wind and current have little if any, effect in lift at this depth.
- Nos. 14 and 15. These were made on a rough day, and the courses (150 and 330) were directly against and with the sea and wind. The current was accurately measured and found to be approximately at right angles to the sea. Towline tensions were greater than shown, as the scales were not set correctly, but the relative tensions are correct as shown. These two tests show that there is slightly more lift when dragging against the sea and wind.

No.1 Feb. 10.

\*Note #2 Speed 2.0; Head wind 10; Head current 0.3. Sea 2'; Towline 70 m; Bight very taut; Length 1200; Section 300; Buoys N---1---2---F Hoohup 42 42 42 42 42 Test 38 39 39 38 No. 3 Feb. 11 Speed 2.8; Head wind 15; Fair current 0.5. Sea 3'; Towline 70 m; Bight medium; Length 3200; Section 400: N---1---2---3---4---5---6---7---F Buoys Hookup 20 20 20 30 40 40 40 40 40 20 20 24 34 - 40 39 37 \*Note #4 and #6 No. 5 Feb. 25 Speed 1.3; Calm; No current; Sea smooth; Towline 125 m; Bight taut; Length 5600; Section 700: N---1---2---3---4---5---6---7---F Hookup 70 80 90 100 100 100 100 100 69 78 86 93 95 95 97 98 Test No. 7 Feb. 26. Speed 2.2; Calm; Fair current, 1.0; Sea smooth; Towline 125 m; Bight taut; Length 1800; Section 300; N---1---2---3---4---5---F Buoys Hookup 48 55 62 62 62 62 -- -- 59 -- --Test No 2 Feb 10 \*Note Speed 2.3; Fair wind, 5; Fair current 0.3; Sea 2°; Towline 70 m; Bight medium; Length 1800; Section 300; N---1---2---3---4---5---F Buoys Hookup 42 42 42 42 42 42 40 40 39 -- -- 41 No. 4 Feb. 25 \*Note Speed 0.8; Calm; Head current 0.3; Sea smooth; Towline 125 m; Bight medium;

Speed 0.8; Calm; Head current 0.3; Sea smooth; Towline 125 m; Bight medium Length 6300; Section 700; (100° bridle—300° straight)\*

Buoys N--1--2--3--4--5--6--7--8--F Hookup 70 70 80 90 100 100 100 100 100 Test 68 -- -- 97 97 98 95 94\* No. 6 Feb.26

### DRAG TESTS

Speed 1.5; Calm; No current; Sea smooth; Towline 125 m; Bight slack; Length 1800; Section 300;

Buoys N---1---2---3---4---5---F Hookup 62 62 62 62 62 62 62 Test 60 59 59 59 59 61

No. 8 March 4

Speed 1.9; Fair wind 12; Fair current 0.4; Sea 3\*; Towline 125 m; Bight taut; Length 6000; Section 600;

Copy for Records Section files.



March 16, 1928.

Pivision of Hydrography and Popography:

Division of Charts:

Tide reducers are approved in volumes of sounding records for

HYDROGRAPHIC SHEET

4748

Locality:

VIRGIN ISLANDS.

G. C. Mattison, 1924-7. Chief of Party: KLA

Plane of reforence is St. Thomas. 1924-5

2.2 ft. on tide staff at 1927

Little Oraz Bay, 1925

Condition of records satisfactory except as checked below:

- 1. Locality and sublocality of survey omitted.
- 2. Month and day of month omitted.
- 3. Time meridian not given at beginning of day's work.
- 4. Time (whether A.M. or P.M.) not given at beginning of day's work.
- 5. Soundings (whether in feet or fathoms) not clearly shown in record.
- 6. Leadline correction entered in wrong column.
- 7. Field reductions entered in "Office" column.
- 8. Location of tide gauge not given at beginning of each day's work.
- 9. Leadline corrections not clearly stated.
- 10. Kind of sounding tube used not stated.
- 11. Sounding tube No. entered in column of "Soundings" instead of "Remarks".
- 12. Legibility of record could be improved.
- 13. Remarks.

( 1.2 ft. on tide staff at Little Gruz Bay, 1927.

Magons Bay 1 1.5 \* đο

Coral Bay · ( 1.5 " do

Chief, Division of Tides and Currents.

#### DEPARTMENT OF COMMERCE

U. S. COAST AND GEODETIC SURVEY

# HYDROGRAPHIC TITLE SHEET

#### WIRE DRAG

The Hydrographic Sheet should be accompanied by this form, filled in as completely as possible, when the sheet is forwarded to the Office.

Field No. 2 REGISTER NO. 4743h State Virgin Islands General locality St. Thomas and St. John Islands Locality Vicinity of St. John and E. St. Thomas Island. Feb. 2,1924 Scale 1-20,000 Date of survey Mar. 21, 1927 ,192 Vessel RANGER Chief of Party G.C.Mattison - C.K. Green Surveyed by C.K. Green, A.P.Ratti, H.E.Finnegan Protracted by A.C.Thorson Soundings penciled by A.C.Thorson Soundings in fathous feet Plane of reference M.T.L. -0.5 ft. Subdivision of wire dragged areas by A.C.Tgorson Inked by A.C.Thorson Verified by.... Instructions dated June 22 ,192 3 Aupplemental February 28,1927. June 22 Remarks: See Hydro. Sheet for this area.