Tide correction problems were identified early in the survey. The problem was not with the tides themselves, but with application of the tide correctors. There were three primary problems. (1) Extraneous and unprintable (viewable) ASCII characters contaminated some tide corrector files such that the tide would not apply when APPLY_TIDES was run, and no error message issued. These were identified early and resolved. (2) A data file time stamp problem was identified in the OPTEK airborne software. When the day changed over at midnight GMT a bit is supposed to be set in the *.fl file. This didn't always happen. However, the time stamp was not reset to zero, just continued. As ping time is derived from the ping counter, the tide correctors were being applied from the wrong day. (3) Four data file format changes occurred of which NAVO was never informed. Three of these affected data time. Addition to these main three problems, a couple of errors were discovered in the tide zone polygon definition files. One polygon was not closed and another had an extraneous point that caused the polygon to cross several others. These errors were all corrected and tides re-applied at NAVOCEANO. Currently, there are no discrepancies in the tide corrections and all soundings are properly corrected.

6.0   **Tides and Water Levels**.

6.1   **General Requirements**. Tidal zoning shall be constructed and tidal data observed and recorded such that derived tidal corrections to the sounding data meet 0.5 meter accuracy standards. The survey area shall be sufficiently zoned and tide gauges strategically located to ensure tidal corrections meet accuracy requirements.

6.2   **Tidal Data Collection, Scope of Work**.

6.2.1   The primary NOAA tide Gauges. Also NOAA CO-OPS was responsible for posting preliminary unverified tidal data on the CO-OPS web site, tidal data processing and verification, posting of verified data to the web site and tidal zoning.

6.3   **Tide Gauges**

NOAA-maintained automatic tide gauges are at the following locations:

    Honolulu Harbor, Oahu
    Mokuoloe, Oahu (northern Kaneohe Bay)
    Nawilili, Kauai
    Kawaihae, Hawaii

6.2.3   **Additional Gauges**. NAVOCEANO installed backup gauges on Oahu at the Barbers Pt. Harbor and the Waianae small craft harbor. On Kauai NAVOCEANO installed a tide gauge at a small craft harbor just south of PMRF between Kekaha and Waimea. NOAA gauges supporting the zoning were located on the windward side of the islands, well away from much of the survey area. The NAVOCEANO installed gauges were installed as a backup to the NOAA gauges. Furthermore, the data from the NAVOCEANO installed gauges were used to confirm the NOAA tide-zoning scheme.